

WASTE PRO TANKS

Used Oil Aboveground Double Wall ULC-5601-07-Latest Standard

Designed for the Storage of Used Oil

The Economical Storage Solution

Standard Design Features:

- · Double wall construction, horizontally built
- · Saddles fully welded
- 1/8" thick steel shell construction
- · Interstice vacuum monitoring gauge with guard
- · 2" male quick coupling in spill box
- · 2" normal vent c/w cap
- · Steel spill box cover with stainless steel hinges c/w splash guard
- · Comes with Level Charts
- Check with installer and local jurisdiction for additionnal norms and regulations.

Tank Exterior:

- · Sandblasted to SSPC-SP6, commercial blast
- E2 Paint system:
- Two part high built epoxy 4-6 mils dry
- Two part Polyurethane epoxy 2-3 mils dry
- · Safety Labeling as per codes
- Product Labeling on three sides
- Paint Warranty for two(2) years from date of manufacturing
- Tank Warranty for a period of five(5) years from date of manufacturing



"This high-quality product undergoes a series of tests and is built to last. Proud and dedicated workmanship goes into the fabrication of every tank."

Options :

٠	15	mil	Int	erio	or	line
	Pu	mpi	ng	sta	ti	on

- · Liquid level gauge
- · Remote collection box
- · Manway & spill box combo
- · Solenoid switch on vacuum gauge

Specifications:

Model	Double Wall	Specifications						
		Dia.	O.A.L.	Shell	Paint	Steps	Fittings	
500 L	•	37,5"	30"	1/8"	Polyurethane epoxy finish	0	Two(2) N.P.T. 2"	
1000 L	•	37.5"	60"	1/8"	Polyurethane epoxy finish	0	Three(3) N.P.T. 2"	
1500 L	•	45"	60"	1/8"	Polyurethane epoxy finish	0	(3) N.P.T. 2"	
2 000 L	•	50"	60"	1/8"	Polyurethane epoxy finish	5	(3) N.P.T. 2"	
2 400 L	•	50"	72"	1/8"	Polyurethane epoxy finish	5	(3) N.P.T. 2"	
3 000 L	•	50"	84"	1/8"	Polyurethane epoxy finish	5	(3) N.P.T. 2"	
4 500 L	•	50"	144"	1/8"	Polyurethane epoxy finish	5	(3) N.P.T. 2"	

Inquire for details

Distributed by: